

Q1 Tower Reaches New Heights in Gold Coast, Australia



| | |
|------------------------|---------------------------------|
| Project | Q1 Tower, Gold Coast, Australia |
| Engineers | Ove Arup & Partners |
| Construction/Developer | Sunland Group LTD. |
| Concrete Supplier | Readymix Concrete |
| GCP Solution | ADVA® 133 superplasticiser |

The Overview

The Project

Q1, the world's tallest residential tower, with its striking architecture, is an impressive enhancement to the Gold Coast skyline. The tower has a 10-storey observatory, as well as the fastest lifts in the Southern Hemisphere. It also has the world's longest spire at 97.5 metres.



"Readymix chose ADVA® 133 superplasticiser for the following reasons: excellent slump control, increased fluidity to assist pumping, minimal retardation at high slumps, high performance finishing, excellent for controlling set times and minimal slump loss."



To construct a commercial building of such height required the very best superplasticiser available, as all concrete needs to be pumped, right up to level 80, some 259 metres above ground. The concrete also had to meet a slump range of 160 mm to 200 mm for different floor levels because of rebar interaction.

Concrete supplier, Readymix, approached GCP Applied Technologies for the new generation ADVA®133 high range water-reducer based on a revolutionary co-polymer technology. It displays superior cement agglomerate dispersing characteristics resulting in lower dosages for higher and better slump control. ADVA®133 superplasticiser allows concrete to be produced with very low water to cement ratios without affecting workability and is ideal for high slump concrete where there is restrictive rebar interaction.

This highly effective superplasticiser allows for quick placement of concrete without segregation or loss of strength for the commercial building.

All concrete was pumped to various levels, with no intermediary pump being used.

The Final Results

The project was struggling to meet deadlines when it reached 50 floors as construction stopped at more than 30 knots wind speed—there were high wind speeds especially from the 60th floors and above. Thanks to the use of ADVA[®]133 and the Readymix mix-design adjustments the project was back on schedule by the time it reached the 80th floor.

gcpat.vn | For technical information: asia.enq@gcpat.com

GCP Applied Technologies Inc., 2325 Lakeview Parkway, Alpharetta, GA 30009, USA

GCP Vietnam Company Ltd, Lot B14, Section B, Street No. 12, Xuan Thoi Son Small Scale Arts & Crafts Group, National Road 22Xuan Thoi Son Village, Hoc Mon District, Ho Chi Minh City

This document is only current as of the last updated date stated below and is valid only for use in Vietnam. It is important that you always refer to the currently available information at the URL below to provide the most current product information at the time of use. Additional literature such as Contractor Manuals, Technical Bulletins, Detail Drawings and detailing recommendations and other relevant documents are also available on www.gcpat.vn. Information found on other websites must not be relied upon, as they may not be up-to-date or applicable to the conditions in your location and we do not accept any responsibility for their content. If there are any conflicts or if you need more information, please contact GCP Customer Service.

Last Updated: 2023-09-29

gcpat.vn/about/project-profiles/q1-tower-reaches-new-heights-gold-coast-australia